

SEEDED GRASS SCHEDULE

	HYDROSEED GRASS. LOW MAINTENANCE SEED MIX BY PREMIER PACIFIC SEEDS, OR APPROVED EQUAL.				
--	--	--	--	--	--

SYMBOL	CODE	QTY	BOTANICAL NAME	COMMON NAME	SIZE
TREES					
	CF	7	Carpinus betulus 'Frans Fontaine'	Frans Fontaine Hornbeam	6cm Cal.

SYMBOL	CODE	QTY	BOTANICAL NAME	COMMON NAME	SIZE	SPACING
SHRUBS						
	EP	93	Echinacea purpurea	Coneflower	#1 Pot	0.5 m
	MC	9	Mahonia aquifolium 'Compacta'	Compact Oregon Grape	#2 Pot	1.2 m
	NT	54	Nassella tenuissima	Mexican Feather Grass	#1 Pot	0.6 m
	PS	15	Pinus mugo 'Slowmound'	Slowmound Mugo Pine	#2 Pot	1.2 m
	PM	19	Polystichum munitum	Western Sword Fern	#1 Pot	1.2 m
	RB	60	Rudbeckia fulgida	Coneflower	#1 Pot	0.5 m
	SA	142	Sesleria autumnalis	Autumn Moor Grass	#1 Pot	0.6 m
	VO	10	Vaccinium ovatum	Evergreen Huckleberry	#2 Pot	1.2 m

PLANTING NOTES

GENERAL PLANTING NOTES:

- CHECK FOR LOCATIONS OF WATER LINES AND ANY OTHER U/G SERVICES PRIOR TO DIGGING.
- TRANSPORT AND HANDLING OF PLANT MATERIALS TO CSLA LANDSCAPE STANDARDS.
- ENSURE AVAILABILITY AND SOURCE OF PLANT LIST MATERIALS AT LEAST 2 WEEKS PRIOR TO ANTICIPATED PLANTING TIME.
- INSPECT ALL ASSEMBLED PLANT MATERIAL UPON ARRIVAL ON SITE, PRIOR TO INSTALLATION.
- NO PLANTS REQUIRING PRUNING OF MAJOR BRANCHES DUE TO DISEASE, DAMAGE OR POOR FORM WILL BE ACCEPTED.
- ALL CALIPRE-STOCK TREES SHALL BE B&B IN WIRE BASKETS OR IN CONTAINERS. BAG-GROWN TREES WILL NOT BE ACCEPTED.
- THE LAYOUT OF ALL APPROVED PLANT MATERIAL SHALL BE IN ACCORDANCE WITH THE CONTRACT DRAWINGS. FINAL LAYOUT IS TO BE VERIFIED BY THE CONTRACT ADMINISTRATOR.
- FOR SEEDING REQUIREMENTS, REFER TO SPECIFICATIONS.
- PLANTING TO OCCUR IN FALL TO ALLOW FOR ESTABLISHMENT IN RAINY SEASON. PLANTS TO BE WATERED AS REQUIRED DURING FIRST YEAR ESTABLISHMENT.
- PLANTING TECHNIQUES AS PER SPECIFICATIONS.

GROWING MEDIUM NOTES:

- GROWING MEDIUM TO MEET THE PHYSICAL AND CHEMICAL PROPERTIES DEFINED IN THE PROJECT SPECIFICATIONS FOR LEVEL 2 "GROOMED" AREAS.
- PRIOR TO PROCUREMENT, INFORM CONTRACT ADMINISTRATOR OF NAME OF GROWING MEDIUM SUPPLIER AND LOCATION OF STOCKPILE FOR INSPECTION.
- (2) ROUNDS OF SOIL TESTING WILL BE REQUIRED AT THE CONTRACTOR'S EXPENSE: (1) PRIOR TO INSTALLATION OF GROWING MEDIUM TO IDENTIFY SUITABILITY AND AMENDMENT REQUIREMENTS; AND (1) AT SUBSTANTIAL PERFORMANCE TO CONFIRM QUALITY OF INSTALLED GROWING MEDIUM.
- FOR SOIL TEST(S): SUBMIT 4 LITRE SAMPLE(S) OF PROPOSED GROWING MEDIUM TO PACIFIC SOILS ANALYSIS INC. LABORATORY IN BURNABY (604) 273-8226. INDICATE TO LAB THAT THE PURPOSE OF ANALYSIS AND AMENDMENT RECOMMENDATIONS ARE FOR 1) TREE AND SHRUB PLANTING; AND 2) SEEDDED LAWN AREAS. ANALYSIS SHOULD INCLUDE ALL PROPERTIES LISTED IN THE PROJECT SPECIFICATIONS.
- THE SOIL SAMPLES AT SUBSTANTIAL PERFORMANCE, ALONG WITH THE AMENDMENT RECOMMENDATIONS FROM THE SOILS LAB, SHALL BE THE BASIS FOR ACCEPTANCE OF THE GROWING MEDIUM.
- MINIMUM GROWING MEDIUM DEPTHS: GRASS AREAS 150mm; SHRUB BEDS 450mm; TREE PLANTING / CONTINUOUS SOIL TRENCHES 1200mm.

MULCH NOTES:

- BARK MULCH DEPTH SHALL BE 75mm (3") AFTER SETTLING.
- PROVIDE MULCH OVER ALL PLANTING AREAS EXCEPT SEEDDED AREAS.
- TO BE NATURALLY DARK BROWN BARK MULCH AND FREE OF WOOD STICKS, STONES, ROOTS, AND OTHER DELETERIOUS MATERIAL.
- SAMPLE TO BE PROVIDED TO THE CONTRACT ADMINISTRATOR FOR APPROVAL PRIOR TO INSTALLATION.



1 PLANTING PLAN  
1:150

LANARC

405 - 256 Wallace Street, Nanaimo, BC V9R 5B3  
Tel (778) 762-4800  
www.lanarcconsultants.ca



6300 Hammond Bay Road, Nanaimo, BC V9T 6N2  
Tel (250) 390-4111  
www.rdn.bc.ca

PRELIMINARY  
NOT FOR CONSTRUCTION

70% Design	GL	JG	25.04.25
100% Design	GL	JG	25.10.30
Issue for Building Permit	GL	JG	25.11.20
Issue for Tender	GL	JG	26.01.13
Issue for Addenda	GL	JG	26.02.02

Issued By Appd YY MM DD

Permit-Seal  
**Extension Community Park: Sport Court Area**  
2120 Ryder Street, Nanaimo, BC

Project  
**Planting Plan**

Title	24559	Project No.	Scale	1:150	5
Drawing No.	L3.0	Permit No.	Revision	A	