



REQUEST FOR PROPOSALS No. 26-034

GNPCC Grit & Sedimentation Tanks 2027 Refit Work

Addendum 7

Issued: Sept 16th, 2026

**Closing Date & Time: on or before 3:00 PM Pacific Time on ~~Sept 1st~~ ~~Sept 15th~~
Sept 22nd, 2026**

This addendum shall be read in conjunction with and considered as an integral part of the Request for Proposals. Revisions supersede the information contained in the original Proposal or previously issued Addendum. No consideration will be allowed for any extras due to any Vendor not being familiar with the contents of this Addendum. All other terms and conditions remain the same.

Request for Proposals Addendum Sections

- a. Respondent questions

End of Addendum 7

Addendum 7a Responses to Vendor Questions

1. Question:

Can you please confirm if there are C channel runners under the steel plate in the Grit Tank1 collector trench that will require removal as part of the trench floor concrete repair, see photos attached from Grit Tank2 for reference.

Answer:

Addendum 1, questions 2 & 3 discuss the overall concrete repair requirements for Grit Tank 1.

The respondent shall assume that there are also 4x C channel runners underneath the plate flush with the bottom. Assume that the runners are 4in height by 2in width. The C-channels shall be removed as part of the repair which will require a localized deeper repair depth, but the overall 1in depth for the remainder of the trench shall be assumed.

See picture below from Grit Tank 2 (2025 scope of work).

